Tulsa Ports

Towboat Dock Replacement Project

BURNS MEDONNELL®

Revision: 90% Design Submittal Date: 7/20/2021 Construction Duration (Mo): 9

Opinion of Probable Cost

					Unit Cost	TOTAL	
0	PROCUREMENT AND CONTRACTING REQUIREMENTS						
	Site and Environmental Permitting		1	LS	200,000.00		200,000
	Engineering Services During Construction (Const Admin, Inspections, material tests)		1	LS	345,000.00		345,000
	icos)				040,000.00	\$	545,000
1	GENERAL REQUIREMENTS						
	Mobilization/Demobilization			LS MO	150,000.00 1,500.00		150,000 13,500
	Administration General Conditions - Staffing (PM Half Time and APM/EIT Full Time)			MO	38,000.00		342,000
	General Conditions - Site Support Mat'l / Equipment			MO	7,500.00		37,500
	Site Temporary Fencing		100		18.00		1,800
	Site Clean Up Labor Builders Risk & General Liability Insurances			MO LS	2,600.00 3,500.00		13,000 3,500
	Builders Historia Elability Historiaes				0,000.00	\$	561,300
2	EXISTING CONDITION					TOTAL	
	Demolish Existing Dock		1	LS	90,000.00	\$	90,000
3	CONCRETE				Sub/LS	TOTAL	30,000
	Pile Fill		236	CY	750.00	\$	177,000
	Retaining Wall			CY	1,500.00		12,000
	Misc Pads		6	CY	750.00	\$	4,500 193,50 0
26	ELECTRICAL				Sub/LS	TOTAL	130,000
	Low Voltage Cable (3/C & 4/C, THHN & Marine)		2,400		14.00	\$	33,600
	Ground Cable (#4/0 Bare Copper)		300			\$	2,400
	Grounding Materials (Jumpers, Rods, Wells) Conduit (All sizes)		2,275		9,500.00 51.00	\$	9,500 116,025
	Conduit Trenching			LF	200.00	\$	914
	Dock/Ramp Lights (C-H, model PMV)		7	EA	3,000.00	\$	21,000
	Area Lights (Cooper Area Lights w/ 25ft Poles) Swivel pole (8ft poles for dock/ramp lights)			EA EA	6,000.00	\$	18,000 8,400
	Low Voltage Transformer (75KVA, 480-120/208V, 3-Ph, Dry-Type, NEMA 3R)			EA	1,200.00 6,500.00		6,500
	Fused Disconnect Switch (600V, 100A, 3-Ph) NEMA 3R w/ Surge		1	EA	2,000.00	\$	2,000
	Non-fused Disconnect Switches (240V, 200A, 3-Ph) NEMA 3R			EA	1,500.00		3,000
	GFCI Receptacles (120V, 15A, Weatherproof enclosure) Panelboard (120/208V, 100A Main CB, 24-Ckt)			EA EA	469.00 5,000.00		1,407 5,000
	Lighting Contactor (6ckt w/ HOA)			EA	1,700.00		1,700
	Unistrut Switchrack			EA	3,900.00	\$	3,900
						\$	233,346
31	EARTHWORK		120		Sub/LS	TOTAL	200.00
	Drill Rock Sockets 72" Casing 84" (\$.85/Lb)		120 72		2,414.00 1,255.00		289,680 90,360
	48" Pipe Pile (\$.85/Lb)		468		443.00		207,324
	Concrete Fill Around Pipe Pile				441.00		44,100
	24" Pipe Piles (\$.85/Lb) Drill Rock Sockets 48"		588 308		218.00 1,297.00		128,184 399,476
	Concrete Fill Around Pipe Pile		106	CY	441.00		46,746
	Remove And Replace Fence for Pump		80		48.00		3,840
	Temp Road for Pump & Trucks		233		12.00		2,796
	Remove Temp Road Diag Bracing for All Piers To hold the pil	les in place for 48 hours	233		7.00		1,63
	Work And Bracing Barge Rental Spud	les III place for 46 flours		TN MO	5,887.00 26,390.00		58,870 52,780
						\$	1,325,787
32	EXTERIOR IMPROVEMENTS				Sub/LS	TOTAL	
	Turbidity Curtain		260			\$	6,500 2,920
	Silt Fence Safety Fence		730 340		4.00 3.00	\$	1,020
	Permanent Seeding		6,500		1.50	\$	9,750
	Inlet Protection		1	EA	300.00	\$	300
	Construction Entrance Concrete Washout Area		<u>1</u>	EA EA	2,500.00 1,000.00		2,50
	Riprap			TON	80.00		66,88
	Earthwork - Cut		1,250		21.00	\$	26,250
	4" Concrete Walkway		130	SY	60.00		7,800
	4" Parking Space Striping Chain Link Fence W/ Barbed Wire & 6' Wide Gate		45 160		2.50 45.00		7,20
	Chain Link I choc W/ Dalbed Wile & U Wide Gate		160	L.	45.00	S	7,200 132.23
33	UTILITIES				Sub/LS	TOTAL	
	2" Schedule 80 PVC Pipe - Water		190			\$	8,55
	Yard Hydrant 2" Schedule 80 PVC Valve & Valve Box			EA EA	600.00 800.00		1,600
	2" Schedule 80 PVC Tee			EA	150.00		1,600
			<u> </u>			\$	10,900
35	WATERWAY AND MARINE CONSTRUCTION				Sub/LS	TOTAL	
	Aluminum gangways, 10'x10' platforms, handrails, and ramps and a concrete floating dock (including freight)		1	LS	426,710.00	•	426,710
	moderny dook (molecumy menym)		1	LO	420,710.00	\$	426,710 426,71 0
	CONSTRUCTION TOTAL					\$	3,518,775
	CONTINGENCIES	Low	-10%			\$	(351,877
	ONTINGENOIS	High	15%			\$	527,816
		Low	-10%			\$	3,166,897
	PROBABLE COST RANGE	High	15%			-	4,046,591
			10/0			T	.,. 10,001
	OTHER POTENTIAL PROJECT COST				Sub/LS	TOTAL	
	OTHER POTENTIAL PROJECT COST				Sub/LS	TOTAL	
	OTHER POTENTIAL PROJECT COST				Sub/LS	TOTAL	
	OTHER POTENTIAL PROJECT COST				Sub/LS	TOTAL	

- Changed Water Line connection from Corporation Stop to 2" Tee with 2" Ball Valve and Valve Box.

 Assumed that a plie embedments will all be rock sockets instead of driven piles.

 Costs for swrk was included, conduit quantity increased, equipment pricing was "trued-up" and labor costs for installation of all equipment was incorporated into the unit pricing.

Tulsa Port of Catoosa

Towboat Dock Replacement Project

Revision: 90% Design Submittal Date: 7/20/2021



Project Schedule

ask Name	Start Date	Due Date	Predecessors	021	October 2021		January 2022		April 2022		July 2022		Oc	October 2022			ry 2023	A	April 2023		July	y 2023		October 202	
	Start Date			Aug Sep	Oct	Nov Dec	Jan	Feb Mar	Apr	r May Jun	Jul	Aug Sep	0	ct No	ov Dec	Jan	Feb M	lar /	Apr Ma	y Jur	Jul	Aug	Sep	Oct Nov	
Grant Awarded	10/1/2021	10/1/2021			•	1																			
Permitting	11/1/2021	10/28/2022	Grant Awarded			<u> </u>																			
Prepare Bid Documents	10/31/2022	11/28/2022	Permitting											C											
Bidding	12/1/2022	12/30/2022	Prepare Bid Documents													1									
Construction NTP	1/6/2023	1/6/2023	Bidding													* -									
SubContracting/Mobilization	1/6/2023	1/23/2023	Construction NTP																						
Shop Drawings	1/23/2023	3/6/2023	SubContracting/Mobilization													Č	3								
Fabricate Docks and Gangways	3/6/2023	7/6/2023	Shop Drawings														ŭ								
Fabricate Piles	3/6/2023	6/6/2023	Shop Drawings	H													ŭ			-3					
Civil and Electrical Site Work	3/6/2023	6/6/2023	Shop Drawings														ŭ								
Pile Driving	6/6/2023	7/6/2023	Fabricate Piles																	Ľ					
Dock and Gangway Installation	7/6/2023	8/7/2023	Fabricate Docks and Gangways																		Č	3			
Electrical Fit out	8/7/2023	9/7/2023	Dock and Gangway Installation																			Ľ	1		
Close Out/Demobilization	9/7/2023	10/5/2023																						1	